



## **PUBLIC INFORMATION REPORT**

### **T-848 HULL DRIVE BRIDGE (YORK COUNTY BRIDGE # 226) OVER BERMUDIAN CREEK WASHINGTON TOWNSHIP, YORK COUNTY, PENNSYLVANIA**

**December 13, 2019**

**Report #1**

#### **PROJECT DESCRIPTION**

This project is a historic truss structure preservation of County Bridge 226, which carries T-848 Hull Drive over Bermudian Creek in Washington Township, York County. The existing truss will be preserved and rehabilitated, with some of the original members being replaced as necessary. Additionally, the stone masonry abutments will be rehabilitated and the existing caissons will be replaced with a concrete pier to ensure a safe bearing for the superstructure. Alignment of the approach roadway, structure clearances, and structure length remain the same upon completion of the project.

#### **TRAFFIC CONTROL**

A detour (approximately 5 miles) will be utilized while the new bridge is being constructed. This bridge is along a school bus route.

#### **PROJECT SCHEDULE OR CONSTRUCTION SCHEDULE**

- Advertise: Completed
- Project Letting: Completed
- Notice to Proceed: December 2019
- Construction Completion: May 2020

#### **FUNDING & COST**

- Construction cost estimate: \$1,860,000

#### **UPCOMING ACTIVITIES**

- Complete intermediate and finish paint coats

- Reset Truss

## **ATTACHMENTS**

